ΕĮ	26273
Miller Compan	Š
H.C.Mille	Stock

28460

DOCUMENT NUMBER

I Robert H. Winat do hereby certify that on the 24th day
of January 19.85., I found
evidence of the meander
corner of5_
Township40. , North, Range
.12 East Fourth Principal Meridian,
as described hereon; and that from this evidence
I established a new monument and accessories
as described hereon to perpetuate the original
location of this corner.
Resident witnesses:
Mike Stevens
ritke prevens
Mike Lukasko

State of Wisconsin

County of Forest

SS.

		9
  - 	/ Ke	ntuck_
 <del>-</del> -		1102-
5		ake
	1 1	
 	-¦	
<b>!</b>	; I	
	1 1	

O = Corner monument restored.

## U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Index No. A 7-8

History of original corner establishment:

Dependent resurvey in 1941 by Guy R. Veal, set a 6"x24" concrete monument with a G.L.O. brass cap.

BT: Elm

7''

S18뉳°E

6 1ks.

Description of corner evidence found:

Found 1" iron pipe up 2". Found 6"x6" broken concrete N64°E 6' from pipe in bank eroded by water. Found 6"x6"x12" concrete piece in water, no base. Found BT's:

White Birch 8" S42°W 9.10' (set nail in tree) Sugar Maple 13" S20°E 4.15' (set nail in tree)

Description of monument and accessories I established to perpetuate the original location of this corner,

Set a 2"x36" aluminum monument with 3" aluminum tablet stamped to identify corner. Blazed and scribed the following BT's:

Sugar Maple 7" Steel Sign Post S50°W East 16.72' to nail in tree

st 2.00'

Reference to Standard Corner between Sections 32 33 T41N, R12E, marked by a G.L.O. Brass Cap; S89°55'50'W, 380.22'.

(over)

Dated at Rhi	nelander ,	Wis., this	day	of June	1985	19
	. /					

gnature Color H Mill Title R.L.S. Registration No. 1040

(CONDEX SOLKEROTE Registered Land Surveyor, MECHANICAL MERCHANICAL ME

Office of Register of Deeds, County of Forest
I hereby certify that the within instrument was filed in this office for record on the 24th day of July 1985

at 1:10 o'clock P. M.

(Register of Deeds)

Z.....Deputy


(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

N/A.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

  Found perpetuated location.
- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

  No.



MC is set 2'X36'' aluminum monument w/3'' aluminum tablet, stamped to identify corner.

or Scal

ROBERT H. WINAT S-1040 RHINELANDER, WIS.

SURV

(i) Robert H. Winat
(type or print name) certify that the corner location shown
on this record was determined by me or under my direction and
control and that this U.S. Public Land Survey Monument Record is
correct and complete to the best of my knowledge and belief.

ignature 1983