

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I, William B. Cochrane, do hereby certify that on the 11th day of May, 1982, I found evidence of the Northeast Section corner of Section 5 Township 39 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Original survey in 1859 by William E. Daugherty  
Dependent resurvey in 1939 by H. D. Craig  
From the remains of the original bearing trees, set a concrete monument, 24" long, 6" in diameter, 18" in the ground, with a brass tablet stamped T4ON, R12E, S32, S33, S5, S4, T39N, 1939  
From which the following bear:  
Sugar Maple, 14", N82E, 34 lks.                      Sugar Maple, 12", S65° 3/4'W, 85 lks.  
Hemlock, 7", S17 1/2'E, 55 lks.                      Sugar Maple, 24", N85° 1/2'W, 73 lks.



Description of corner evidence found:

Found monument as described and in place  
Sugar Maple, 23", N82E, 22.44 ft.  
Hemlock, 15", S17 1/2'E, 36.30 ft.  
Sugar Maple, 23", S65° 3/4'W, 56.10 ft.  
4" x 4" Cedar post 0.50 NE of monument

Description of monument and accessories I established to perpetuate the location of this corner:

Blazed and scribed the following new bearing tree:  
Hemlock, 21", N41W, 72.12 ft.

DOCUMENT NO.  
**124410**



● - Corner monument restored  
□ -

Resident witnesses \_\_\_\_\_  
Dated at Hiles Wisconsin, this 20th day of July 1982.  
Signature William B. Cochrane Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)  
Surveyors Registration No. S-1107

Office of Register of Deeds County of Forest  
I hereby certify that the within instrument was filed in this office for record on the 7th day of October 1983, and was filed in Book No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.

Signature Eugene Staszny Title Register of Deeds

Township 39 North, Range 12 East, Section 5, Index No. A-9, Page No. \_\_\_\_\_

44012320000