

DETAIL SUMMARY OF MISCELLANEOUS QUANTITIES

STATE PROJECT NUMBER	SHEET NO.
9 3 3 9-3 - 70	
MISCELLANEOUS QUANTITIES	
FOR	
FOREST COUNTY	
C.T.H. " S"	

SODDING

STATION	STATION	LOCATION	SQ. YD.
276+00	280+00	DT. LT.	450
306+00	312+00	DT. LT.	670
274+00	279+00	DT. RT.	565
300+00	301+00	DT. RT.	120
306+00	311+00	DT. RT.	565

CLEARING & GRUBBING

STATION	STATION	LOCATION	STATIONS
267+00	349+00	MAINLINE	82

SIDE ROAD & PRIVATE ENTRANCE PIPES

STATION	LOCATION	DIA. IN.	LENGTH	TYPE	R.C.C.P. CLASS	THICKNESS (INCHES) STEEL ALUMINUM	APRON ENDWALLS
9+30	WOLF RIVER RD.	24	36 LIN. FT.	C.P.	111	.064	2
337+46	PE. RT.	18	50 LIN. FT.	C.P.	111	.064	2
346+40	PE. LT.	18	50 LIN. FT.	C.P.	111	.064	2

BITUMINOUS CONCRETE

LOCATION	TON
MAINLINE	2402
SIDE ROADS	38

EROSION MAT

STATION	STATION	LOCATION	SQ. YD.
278+00	279+00	DT. LT.	110
278+00	279+00	DT. RT.	115
310+00	311+00	DT. RT.	115

BITUMINOUS MATERIAL FOR SURFACE COURSE

LOCATION	TON
MAINLINE	147
SIDE ROADS	3

CROSS DRAINS

LOCATION	DIA. IN.	LENGTH LIN. FT.	TYPE	R.C.C.P. (CLASS)	THICKNESS (INCHES) STEEL ALUMINUM	APRON ENDWALLS
282+00 &	24	66	C.P.	111	.064	2
342+00 &	24	76	C.P.	111	.075	2
313+50 &	24	68	C.P.	111	.064	2

RIGHT - OF - WAY MARKER POSTS

STATION TO STATION	NO. REQUIRED
267+00 283+00	1
283+00 310+00	2
310+00 335+00	10
335+00 348+57.66	5

CRUSHED AGGREGATE BASE COURSE

BASE	CU. YDS.
MAINLINE	6700
SIDE ROADS	80
SHOULDER3	
MAINLINE	536
SIDE ROADS	4
PE.	30